

DETAIL SUMMARY OF MISCELLANEOUS QUANTITIES

UNCLASSIFIED EXCAVATION:

<u>Location</u>	<u>Cu. Yds.</u>
Cross Sections	10,743
Sta. 420+00 - Offtake ditch Rt.	20
Sta. 425+08 - " Rt.	20
Sta. 469+00 - Special ditch Rt.	25
Sta. 474+00 " Rt.	50
Undistributed	142
Total	11,000

GRUBBING:

<u>Sta. - Sta.</u>	<u>Stations</u>
390+00-476+00	0
476+00-483+00	7
483+00-486+00	0
Total	7

GRAVEL OR CRUSHED STONE BASE COURSE:

<u>Location</u>	<u>Cu. Yds.</u>
390+00 - 486+00 Base	5,568
390+00 - 486+00 Shoulders	480
20 P.E.'s at 15 CY/each	300
Town Road Sta. 472+00	125
Undistributed	127
Total	6,600

GRANULAR SUBBASE COURSE:

<u>Location</u>	<u>Cu. Yds.</u>
390+00 - 486+00	11,712
Side Roads & P.E.'s	188
Total	11,900

CULVERT PIPE:

<u>Station</u>	<u>LOCATION</u>		<u>C U L V E R T P I P E</u>				<u>MARKER POSTS</u>
	<u>Lt.</u>	<u>Rt.</u>	<u>18"</u>	<u>24"</u>	<u>30"</u>	<u>36"</u>	
401+48	X	X	30				8
404+00					52		12
409+05	X		30				8
420+05	X				52		12
429+80	X		30		52		12
436+47							8
443+60	X		30	56			10
447+93	X					50	8
472+00		X			30		16
474+50	X		30				12
482+82		X					8
Undistributed			60	56	186	50	16
TOTAL			210	56	186	50	130

PROJECT	SHEET NO	TOTAL SHEETS
S 0570 (4)	3	30