

ESTIMATE OF QUANTITIES

CONTRACT NO. 4 (174-17)
 ROAD AND BASE COURSE

PROJECT DESIGNATION	SHEET NO.
HHS - 001(4) / 1174-2-70	
Estimate of Quantities For	
S. H. 51	Lincoln County

SEC NO.	STATION TO STATION	NET LENGTH OF CENTER LINE	CONSTRUCT PASSING AND TURNING LANES
	ITEM NO.		9000
	UNIT	LIN. FT.	LUMP SUM
	14+5 - 23+5	900	1
	TOTAL	900	1

MISCELLANEOUS QUANTITIES

UNCLASSIFIED EXCAVATION	233 CU. YDS.
CRUSHED AGGREGATE BASE COURSE	340 CU. YDS.
CONCRETE PIPE, CLASS III, 24 INCH	17 LIN. FT.
TOPSOIL	545 SQ. YDS.
FERTILIZER	1 CWT.
SEEDING	16 POUNDS

GENERAL NOTES

1. When the quantity of the items of base course and Bituminous Roadmix are measured for payment by the cubic yard or square yard the depth or thickness of the course shown on the plans is approximate and the actual thickness will depend on the distribution of the material as directed by the engineer.
2. Length of runoff and rates of superelevation on curves shall be constructed to match conditions of existing pavement.
3. Topsoil shall be placed to an approximate depth of 3" at time of placing.
4. Seed used shall meet requirements for seed mixture #2 of the Standard Specifications.
5. Utilities affected by this contract shall be notified by the County prior to starting work.

APPLICABLE STANDARD DETAIL DRAWINGS

- | | |
|--------|---|
| 9A1-2 | Design and Layout details for Side Road At-Grade intersections. |
| 15C1-3 | Construction Barricade. |