BASE	OVERLAY	DRG. NO.



POWER DISTRIBUTION RISER DIAGRAM
NO SCALE 120/240 volt, single phase

SERVICE ENTRANCE/DISTRIBUTION NOTES

Existing overhead secondary feed to the Forestry Building is to be removed by the Electrical Utility. The Electrical Contractor shall provide new electrical service from the existing main service panel, prior to removal of overhead service. Provide new 3-#3 XHHW underground to existing meter socket location; remove meter socket, mast and conductors to Forestry Building main device, provide LB entrance fitting at exterior of building, and install new conductors to Forestry Building Main. Coordinate outage of power with the owner. Disconnection of service shall be permitted only after prior notification and approval of the owner.

Coordinate installation of underground raceway for new feeder with the General Contractor, to clear new addition footings. Raceways from main panel to below grade at existing main panel shall be exposed Rigid Steel provided with seal offs at existing panel and rise above grade at forestry building. At Contractor's option, PVC raceway may be used if enclosed in minimum 8" block from not less than 18" above existing building floor to below grade. Exposed raceway at exterior of Forestry building shall be heavywall steel or concrete encased PVC.



Lighting Fixture Schedule

Type 1
Lithonia TXL 250S ARW 240/2F
General Electric U1G253AS1SE6/2F
Crouse Hinds mxR259CN5S/2F
Lamp with 1-LU 250

Suspended high pressure sodium 'Low-Bay' type fixture with spun or formed faceted specular aluminum reflector, acrylic diffuser, cast ballast housing/heatsink (40°C ambient min. rating), with separate ballast fusing (240 Volt or multitap). Provide with safety chain/ retainer for ballast, reflector and refractor. Suspend from unistrut bracing secured to structure with bottom of reflector flush with bottom of structure.

Type 2
Hitek (Lithonia) TWP 150S 120
Crouse Hinds WAL 15SP2120A 1046
Hubbell PVL 0150S 111
Lamp with 1-LU 150

High pressure sodium wall mounted area light with fused, -20°F ballast. Mount to exterior wall of building, at 15'-0" above grade to center of fixture. Provide with singe photocell control for dusk-to-dawn lighting control.

Type 3
Lithonia AF240 120ES
Metalux IA240 120 ES
Keystone KL240 120ES
Lamp with 2-F34LW

Surface industrial fixture with symmetrical reflector. Mount tight to underside of structure at alternate bid storage area. Provide entire fixture chassis and reflector with thermoset polyester power or baked porcelain enamel finish.

Exits
Lithonia XS-R-EL series
Emergency Light SMX1-R series
Dual Lite E-RWW-DC-6V series
Lamps as required by manufacturer

Self contained emergency exit light including all lead or lead-calcium battery, charger, transfer electronics, protected by deep discharge and overcharge cutouts. Provide with status LED and test pushbutton accessible from face of unit.

SYMBOL SCHEDULE

- Lighting Fixture Outlet
- Surface or Suspended Lighting Fixture
- Wall or Bracket Mounted Fixture
- Exit Fixture – Shading indicates Illuminated Face(s)
- S Single Pole Toggle Switch
- S_3 Three-Way Toggle Switch
- Duplex 120 VAC Receptacle
- Disconnect Switch
- (M) Motor Connection. 'F' Denotes Fractional Horsepower
- C Conduit
- EC Electrical Contractor
- EF Exhaust Fan
- MT Empty

NOTE:
All conduit installed within the vehicle repair and storage areas must comply with NEC Chapter 5, Article 511 in particular. No conduit shall pass through the plane at 18" above the floor unless it is threaded rigid steel raceway provided with sealoffs and installed as required by NEC Chapter 5.

FLOOR PLAN - ELECTRICAL
1/8"=1'-0"

WHA
WALT HESTEKIN ASSOCIATES, LTD.
Consulting Engineers
P.O. Box 447, Eau Claire, WI 54702-0447
TELEPHONE: (715) 83 - 1709
WHA NO. 88104

NO.	BY	DATE	REVISIONS	ITEM	DESIGN	CHECKED

ENGINEERS ■ ARCHITECTS ■ PLANNERS

LINCOLN COUNTY
VEHICLE STORAGE ADDITION
TOMAHAWK, WISCONSIN

ELECTRICAL PLAN

89003
AUG 1988

E1