

S.P.R. DIVISION	PROJECT	SHEET NUMBER	TOTAL SHEETS
4	TO189 (3)	8	30

STA. 442+00-443+40 LT
STRAW MULCH REQ'D
467 SQ. YD.

STA. 458+00-459+00 LT
INTERCEPTING EMBANKMENT REQ'D.
50 C.Y. WASTE

STA. 458+50 LT.
BACKSLOPE SOD FLUME REQ'D.
85 SQ. YD.

STA. 464+00 LT & RT.
BACKSLOPE SOD FLUME REQ'D.
85 SQ. YD. LT.
85 SQ. YD. RT.

STA. 469+11
RESTORE TWN. RD. APPROACH LT.
TYPE "E" INTERSECTION

SO189(6)
18-21

EASEMENT FOR MARSH DISPOSAL

P.O.I. 462+21.6

P.O.I. 462+21.6

EASEMENT FOR MARSH DISPOSAL

STA. 440+00-470+00 LT. & RT.
8 POSTS REQ'D. FOR R/W

STA. 463+55-465+50 LT & RT.
INTERCEPTING EMBANKMENT REQ'D.
200 C.Y. WASTE

BENCH MARKS

NO.	STATION	DESCRIPTION	ELEV.
35	446+58	SPIKE IN 14" ASH 120' RT.	970.23
36	454+75	NO DESCRIPTION APPROX. 130' RT.	999.66
37	469+25	SPIKE IN 12' WHITE BIRCH 140' RT.	1001.69

STA. 441+00-449+00 RT.
STRAW MULCH REQ'D
3200 SQ. YD.

WITNESS FOR
LAND MONUMENT

STA. 440+00-450+00 RT.
11 MARKER POSTS REQ'D.

STA. 453+00-458+00 RT.
5 MORTAR RUBBLE DITCH CHECKS
23 SQ. YDS. SOD REQ'D.
41 CU. YDS. MORTAR RUBBLE MASONRY REQ'D.

NET CENTERLINE LENGTH STA. 440+00 - 470+00 = 3000.0 LIN. FT.

C 68,816
F 59,110
B 10,250
SHG 34%

