



P. I. 616+22.42  
 Δ 53° 50' 03" RT.  
 D. 1° 00'  
 T. 2,908.93'  
 L. 5,383.42'  
 S.E. 0.027'/'  
 R.O. 175'

NET CENTERLINE LENGTH STA. 600+00 - STA. 630+00 = 3,000.00 LIN. FT.

BENCH MARKS			
NO.	STATION	DESCRIPTION	ELEV.
18	609+80	BOLT IN 8" NORWAY PINE	96' LT. 1681.94
19	622+25	BOLT IN 12" OAK	68' LT. 1680.00

UNCL.	0	CU. YD.
FILL	5,733	CU. YD.
SHG	40%	
BORROW	8,026	CU. YD.

