

CERTIFIED LAND CORNER RESTORATION


Index No. I-15

State of Wisconsin }  
County of Lincoln } ss.

I Sheridan D. Schwark, do hereby certify that on the 12th day of April, 1978, I found evidence of the North one-quarter corner of Section 15 Township 31, North, Range 6 East, Fourth, Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

.....  
.....  
.....



○ = Corner monument restored.

History of original corner establishment:

Date: March, 1852  
Surveyor: A.G. & F.S. Ellis  
Monument: Wood post  
Witnesses: 12" Pine S37°E 30 links  
16" " N80°W 77 "

Description of corner evidence found:

We found a 1" solid steel bar in the intersection of California and Water Street which fit the ties on record at the City Engineer's office. The ties had been filed by Becher-Hoppe Engineers of Schofield, Wisconsin. We contacted Don Frisque (R.L.S.) manager of Land Survey Department for Becher-Hoppe, to ask if he wanted to tie in corner. He said we should go ahead and tie it in. While digging the 1" steel bar out, we found a stone monument below the bar with a drill hole in the top. This was the same type of stone that we've found in other areas in the Town of Scott, set by Louis Kleinschmidt in 1903.

Description of monument and accessories I established to perpetuate the original location of this corner.

We set a Lincoln County Berntsen monument with the following witness monuments:  
the south side of the base of a stop sign bearing, N25°W 45.09'  
P.K. nail set in telephone pole bearing N61°E 52.67'  
P.K. nail set in power pole No. 128 ccl-259-66, bearing S53°E 36.21'  
center top of fire hydrant No. 259, bearing S43°E 31.42'  
1 1/4" iron rod bearing South, 33.00'

Dated at Merrill, Wis., this 14th day of April, 1978.

Signature Sheridan D. Schwark Title Registered Land Surveyor Registration No. S-1205  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of \_\_\_\_\_, I hereby certify that the within instrument was filed in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_ at \_\_\_\_\_ o'clock \_\_\_\_\_ M.

.....  
(Register of Deeds)

By \_\_\_\_\_ Deputy