


CERTIFIED LAND CORNER RESTORATION

Index No. M-5

State of Wisconsin }  
County of Lincoln } ss.

I Sheridan D. Schwark, do hereby certify that on the 5th day of June, 1978, I found evidence of the Northwest corner of Section 20 Township 31, North, Range 6 East, Fourth, Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:



○ = Corner monument restored.

History of original corner establishment:

Date: March, 1852  
Surveyor: A.G. & F.S. Ellis  
Monument: Wood Post  
Witnesses: 18" Sugar Maple, N42°E, 8 links  
18" Birch, S25°W, 44 links

Description of corner evidence found:

We excavated the road intersection and found a 6" x 6" stone monument approximately 2.5' below the road surface. It appears that the top of the stone was broken off, because the stone was not as long as ones we had found previously in the Town of Scott. The stone monuments were set in 1903 by Louis Kleinschmidt (Land Surveyor) There is a map of his resurvey in the Register of Deeds office in the Courthouse.

Description of monument and accessories I established to perpetuate the original location of this corner.

We set a Lincoln County Berntsen Monument above the stone having the following witness monuments:

- 1 1/4" x 30" solid round iron rod set approximately 3' North of Joe Snow, Snow Hill Road sign bearing N37°E, 41.79'
- 1 1/4" x 30" solid round iron rod set approximately 3' East of stop sign bearing S35°W, 36.97'
- 1 1/4" x 30" solid round iron rod set approximately 3' North of guy pole No. 3106-19E1 bearing S48°W, 37.10'
- 1 1/2" iron pipe found in place approximately 3' Northeast of power pole No. 3106-18R15 bearing N42°W, 35.88'

Dated at Merrill, Wis., this 23rd day of June, 1978.

Signature Sheridan D. Schwark Title Registered Land Surveyor Registration No. S-1205  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of \_\_\_\_\_, I hereby certify that the within instrument was filed in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_ at \_\_\_\_\_ o'clock \_\_\_\_\_ M.

(Register of Deeds)

By \_\_\_\_\_ Deputy