

CERTIFIED LAND CORNER RESTORATION

Index No. 5-9

State of Wisconsin }
County of Lincoln } ss.

History of original corner establishment:

I Sheridan D. Schwark do hereby certify that on the 3rd day of January, 1978, I found evidence of the East one-quarter corner of Section 29 Township 31, North, Range 7 East, Fourth, Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Date: February & March, 1852
Surveyor: A.G. & F.S. Ellis
Monument: Wood post
Witnesses: 10" Hemlock N24°W, 16 links
10" Birch N79°E, 14 links

Description of corner evidence found:


The corner was set by single proportionate measure between existing Northeast and Southeast section corners because of lack of any physical or record evidence.

Resident witnesses:

.....
.....
.....

Description of monument and accessories I established to perpetuate the original location of this corner.

We set a Lincoln County Berntsen monument with the following witness monuments:
1" x 30" iron pipe set 1' South of fence post bearing N49°E, 10.60'
1" x 30" iron pipe set 1' West of 16" Bur Oak bearing S78°E, 69.90'
1" x 30" iron pipe set bearing S14°W, 7.60'
1" x 30" iron pipe set 1' East of 14" Bur Oak, bearing S77°W, 87.17'
NOTE: This corner is Westerly of the Railroad right-of-way.



○ = Corner monument restored.

Dated at Merrill, Wis., this 28th day of April, 1978.

Signature Sheridan D. Schwark Title Registered Land Surveyor Registration No. S-1205
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of _____, I hereby certify that the within instrument was filed in this office for record on the _____ day of _____, 19____ at _____ o'clock _____ M.

.....
(Register of Deeds)

By _____ Deputy