

CERTIFIED LAND CORNER RESTORATION


Index No. M-23

State of Wisconsin }
County of Lincoln } ss.

I, Sheridan D. Schwark, do hereby certify that on the 15th day of November, 1979, I found evidence of the South one-quarter corner of Section 13 Township 32, North, Range 7 East, Fourth, Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

.....
.....
.....



○ = Corner monument restored.


History of original corner establishment:

Date: April 1852
Surveyor: A.G. & F.S. Ellis
Monument: Wood Post
Witnesses: 8" Birch, N38°E, 13 links
10" Birch, S42°E, 39 links

Description of corner evidence found:

We found a 6" x 6" x 34" red granite monument at a fence intersection. The monument had been heaved out by frost. We reset the stone at its base location which was also the fence intersection. The stone was the same type we had found in the area before.

Description of monument and accessories I established to perpetuate the original location of this corner.



NOTE: ALL TIE POINTS ARE P.K. NAILS SET IN TREES.
□ = 6" x 6" RED GRANITE MONUMENT RESET

Dated at Merrill, Wis., this 26th day of November, 1979.

Signature Sheridan D. Schwark Title Registered Land Surveyor Registration No. S-1205
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of _____, I hereby certify that the within instrument was filed in this office for record on the _____ day of _____, 19____ at _____ o'clock _____ M.

(Register of Deeds)

By _____ Deputy