

CERTIFIED LAND CORNER RESTORATION

Index No. S-17


State of Wisconsin }  
County of Lincoln } ss.

History of original corner establishment:  
Wood post set by original Government Surveyor

I Sheridan D. Schwark, do hereby certify that on the 1st day of October, 19    , I found evidence of the West one quarter corner of Section 26 Township 33, North, Range 6 East, Fourth, Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:


.....  
.....  
.....



○ = Corner monument restored.

Description of corner evidence found: I set this corner at the intersection of 2 blazed lines, one from the East and one from the South. Although records show that Francis Fox set this corner during the remonumentation of Rock Falls I was unable to find any evidence of his corner or bearing trees. I did find an old weathered wood post which I assume was the original corner. The blaze lines were lines which have been perpetuated by the Lincoln County Crew from work which Francis Fox did. There were also corner plaques nailed on the Cedar B.T. northeast of the corner, these are Owen Illinois plaques, I checked with Bill Stuth of Owen Illinois on a corner location and he said that their records show traverses to the corner they never mention an actual corner. Therefore I reestablished this corner at the location of the wood post which fit the blazed lines.

Description of monument and accessories I established to perpetuate the original location of this corner.



Dated at Merrill, Wis., this 11th day of March, 1985

Signature Sheridan D. Schwark Title Registered Land Surveyor Registration No. S-1205  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19..... at..... o'clock..... M.

.....  
(Register of Deeds)

By..... Deputy



PROPERTY FOR GOVERNMENT COUNTY  
STURRING  
27 26 3  
P6 E









