

CERTIFIED LAND CORNER RESTORATION


Index No. 0-1

State of Wisconsin }  
County of Lincoln } ss.

I LaVerne H. Mosher do hereby certify that on the 27th day of May, 1983, I found evidence of the Southwest corner of Section 30 Township 31 North, Range 6 East, Fourth, Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Arnold Wyland, Jr.



○ = Corner monument restored.

History of original corner establishment:

Notes of the original government survey indicate wood posts were set at all section and quarter-section corners. Stone monuments subsequently were placed at these corners during remonumentation surveys.

Description of corner evidence found:

Excavated roadway with backhoe. At depth of 6 inches below gravel roadway surface a 6"x8"x33" Limestone monument was recovered. Top had been shattered and monument was tipped slightly to South. Top 10 inch piece was still in place but fractured. Bottom 23 inches of stone were in excellent shape, hence a new chisel "X" was cut into center top. Monument was straightened and temporary ties taken. Bottom 23 inch segment was reset in original location such that top is positioned 5 inches below roadway surface. Set 1"x36" iron pipe along North side of monument to aid future location.

Description of monument and accessories I established to perpetuate the original location of this corner.

See sketch on reverse



Dated at Schofield, Wis., this 2nd day of June, 1983

Signature LaVerne H. Mosher Title Registered Land Surveyor Registration No. S-1188  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of \_\_\_\_\_, I hereby certify that the within instrument was filed in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_ at \_\_\_\_\_ o'clock \_\_\_\_\_ M.

(Register of Deeds)

By \_\_\_\_\_ Deputy

RECEIVED AT LINCOLN COUNTY  
COURTHOUSE THIS 6 DAY  
OF June 1983.  
Est. Risher  
TAX DESCRIPTION OFFICE

