

CERTIFIED LAND CORNER RESTORATION


Index No. S-13

State of Wisconsin }  
County of Lincoln } ss.

I Sheridan D. Schwark, do hereby certify that on the 18th day of April, 1979, I found evidence of the West one-quarter corner of Section 27, Township 31, North, Range 6 East, Fourth, Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

.....  
.....  
.....



○ = Corner monument restored.


History of original corner establishment:

Date: March, 1852  
Surveyor: A.G. & F.S. Ellis  
Monument set: Wood post  
Bearing Trees: 14" Sugar Maple, S72°E, 22 links  
8" Sugar Maple, N26°W, 14 links

Description of corner evidence found:

We found a 6"x6" granite monument at the intersection of the centerlines of Scott Road and School Avenue, it was buried 11" under the road surface. The stone was the same type as we've found in other areas in the Town of Scott. The stone were set in 1903 by Louis Kleinschmidt. His map is on record in the Register of Deeds office in the Lincoln County Courthouse.

Description of monument and accessories I established to perpetuate the original location of this corner.



Reference Markers NOTE: We set a 1" iron pipe at the south edge of the stone.  
1) 1" x 30" iron pipe set, N54°W, 43.26'  
2) 1" x 30" iron pipe set 1' more or less south of power pole no. 3106-27W10, N50°E, 40.60'  
3) 1" x 30" iron pipe set 1' more or less east of a road sign, S54°W, 36.96'  
4) 1" x 30" iron pipe set 1' more or less east of an underground tele. box, S32°E, 70.31'

Dated at WAUSAU, Wis., this 19th day of APRIL, 1979.

Signature Sheridan D. Schwark Title Registered Land Surveyor Registration No. S-1205  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of....., I hereby certify that the within instrument was filed in this office for record on the.....day of....., 19..... at.....o'clock..... M..

.....  
(Register of Deeds)

By.....Deputy