

# TAYLOR COUNTY U.S. PUBLIC LAND SURVEY MONUMENT RECORD

## Original Corner Information

Original corner monument: post  
Set by: William E. Daugherty  
Year: 1861

	Bearing Trees			
Species:	sugar	birch	hemlock	sugar
Diameter:	22"	12"	12"	20"
Bearings:	N 48° W	S 70° W	S 39° E	N 28° E
Distance:	23 links	35 links	52 links	22 links

RECEIVED AT LINCOLN COUNTY  
COURTHOUSE THIS 8<sup>TH</sup> DAY  
OF March ~~18~~ 2000  
Jerry Dullman  
LAND INFORMATION OFFICE

## Original Evidence Found – Subsequent Corner Restorations

(Include year of search, name of surveyor, evidence found and monument set.)  
date?, A. W. Kordick, "old cor. with iron & and sq. wooded post at this place, set 2" iron pipe & sq. wooden post inscribed... New B.T. Maple 6" S33E 19.7', New B.T. Birch 24" S86E 32.5', New B.T. Elm 10" N64W 39'

## Basis For Monument Location

After searching for and finding no evidence of the original corner. I accepted a found 1-½" I.D. x 30" iron pipe and Maple and Elm bearing tree evidence as described in the above mentioned Kordick survey as the best available evidence of this corners location.

## Tie Sketch

( Show type of monument set, at least four ties, fence lines, roads and topography.)

I, hereby certify that the information shown hereon is correct and complete to the best of my knowledge and belief.

- ⊕ FOUND 1-½" I.D. X 30" IRON PIPE SET WHITE VINYL POST ALONGSIDE
- SET 1" X 30" REBAR W/2" ALUM. CAP AND WHITE VINYL POST

