

CERTIFIED LAND CORNER RESTORATION


Index No. 0-13

State of Wisconsin }  
County of Lincoln } ss.

I Lester J. Schmit, do hereby  
certify that on the 8th day  
of May, 1979, I found  
evidence of the Northeast  
corner of Section 33  
Township 34, North, Range  
7 East, Fourth, Principal Meridian,  
as described hereon; and that from this evidence  
I established a new monument and accessories  
as described hereon to perpetuate the original  
location of this corner.

Resident witnesses:

.....  
.....  
.....



○ = Corner monument restored.

History of original corner establishment:

Surveyor: Jackson L. Prentice  
Date: December 1854  
Monumentation: Wood Post  
Witnesses: 10" Spruce, S44° W, 25 lks.  
12" Pine, N 69° W, 41 lks.  
12" Pine, N 33° E, 63 lks.  
10" Birch, S 47° E, 20 lks.

Description of corner evidence found:

A 6" x 6" x 30" concrete marker, broken in two pieces, for corner, with  
a 1" iron pipe on the easterly side. 6" square wood post as reference  
being Northwesterly of corner.

Description of monument and accessories I established to perpetuate the original location of this corner.

Berntsen Monument - 30"

3/4" iron pipe, N 89° E, 36.63'  
3/4" iron pipe, S 1° W, 31.46'  
3/4" iron pipe, N 89° W, 30.10'  
3/4" iron pipe, N 8° W, 50.79'

Dated at Tomahawk, Wis., this 8th day of June, 1979

Signature Lester J. Schmit Title Land Surveyor Registration No. S-1192  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of \_\_\_\_\_, I hereby certify that the within  
instrument was filed in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_  
at \_\_\_\_\_ o'clock \_\_\_\_\_ M.

.....  
(Register of Deeds)

By \_\_\_\_\_ Deputy