

CERTIFIED LAND CORNER RESTORATION


Index No. Y-25

State of Wisconsin }
County of Lincoln } ss.

I Lester J. Schmit, do hereby
certify that on the 1st day
of October, 1976, I found
evidence of the Southeast
corner of Section 36
Township 35, North, Range
5 East, Fourth, Principal Meridian,
as described hereon; and that from this evidence
I established a new monument and accessories
as described hereon to perpetuate the original
location of this corner.

Resident witnesses:

Theodore Schmit Jr.



○ = Corner monument restored.

History of original corner establishment:

Surveyor: James M. Marsh
Date: 12 August 1851
Monumentation: Wood Post
Witnesses: White Pine 12; S 70° E, 15 links
Birch 10; S 67° W, 20 links
Tamarack 7; N 27° W, 28 links
Tamarack 10; N 58° E, 30 links

Description of corner evidence found: I found a P.K. nail at the intersection of Loop Road and South River Road. A long time local resident, Theodore Schmit Jr. said that this was the point which had been used for said corner and that he had seen an iron pipe at this location back in the 1940's.

Description of monument and accessories I established to perpetuate the original location of this corner.

Berntsen Monument - 30" (set 2" below the surface of Loop Road)

P.K. Nail in 21" White Pine; N 22°00'36" E; 87.39'
P.K. Nail in 7" Maple; S 08°00'38" E; 176.83'
3/4" iron rod; S 44°31'02" W; 48.76'
3/4" iron rod; N 44°11'34" W; 51.36'

Dated at Tomahawk, Wis., this 6th day of September, 1977.

Signature Lester J. Schmit Title Land Surveyor Registration No. S-1192
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of _____, I hereby certify that the within
instrument was filed in this office for record on the _____ day of _____, 19____
at _____ o'clock _____ M.

(Register of Deeds)

By _____ Deputy