

CERTIFIED LAND CORNER RESTORATION


Index No. C-17

State of Wisconsin }
 County of Lincoln } ss.

I, Lester J. Schmit, do hereby certify that on the 21st day of May, 1976, I found evidence of the West ¼ corner of Section 2 Township 35, North, Range 6 East, Fourth, Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

.....



○ = Corner monument restored.

History of original corner establishment:

Surveyor; Alfred Millard
 Date: 22 October 1861
 Monumentation: 1" X 24" iron rod
 Witnesses: W. Pine 20 N 30° E 92 LKS.
 Y. Pine 16 S 47° W 108 LKS.

Description of corner evidence found:

1" X 24" iron rod, 4" below surface of the ground along the centerline of Town Road.
 Witnesses: P.K. Nail in 18" White Pine; S 32°30' E; 75.9"
 P.K. Nail in P.P. #3506; S 28°30' W; 73.2
 3R29
 P.K. Nail in P.P. #3506; N 32°30' W; 78.3'
 3E19

Description of monument and accessories I established to perpetuate the original location of this corner.

Berntsen Monument - 30" (Set 4" below surface of road)
 Placed 1" X 24" iron rod adjacent to Berntsen Monument, with top of said iron rod 12" below surface of road. Berntsen Monument is West ¼ corner of Section 2.

Witnesses: P.K. Nail in P.P. #3506; N 20° E; 63.47"
 2W17

Dated at Tomahawk, Wis., this 11th day of June, 1976

Signature Lester J. Schmit Title Land Surveyor Registration No. S-1192
 (County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of _____, I hereby certify that the within instrument was filed in this office for record on the _____ day of _____, 19____ at _____ o'clock _____ M.

.....
 (Register of Deeds)

By..... Deputy