

CERTIFIED LAND CORNER RESTORATION

Index No. E-7

State of Wisconsin }  
 County of Lincoln } ss.

I John H. Fisher, do hereby certify that on the 20 day of October, 1983, I found evidence of the South One Quarter corner of Section 5 Township 35, North, Range 6 East, Fourth, Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:  
None

History of original corner establishment:  
 The original government survey was performed by Alfred Millard, Deputy Surveyor, October, 1860 to July, 1861

Wood Post Set

Yellow Pine	18"	S67°W	100 links
Yellow Pine	12"	N66°E	141 links

Description of corner evidence found:


1" iron pipe one foot north centerline of Graf Road

Cedar Stump	6"	S32°E	27.4 feet
Cedar Stump	5"	S12°W	26.5 feet
Cedar	6"	S41°E	56.1 feet
Cedar	5"	S18°W	37.7 feet


Description of monument and accessories I established to perpetuate the original location of this corner.

Replaced 1" iron pipe with Lincoln County Berntsen Monument stamped to identify corner,

Set nail in Cedar	6"	S41°E	56.12 feet
Set nail in Cedar	5"	S19°W	37.80 feet
Set nail in Cedar	6"	S 4°E	44.32 feet
Set nail in Cedar	5"	S42°W	50.72 feet



○ = Corner monument restored.



Dated at Minocqua, Wis., this 27th day of October, 1983.

Signature John H. Fisher Title Registered Land Surveyor Registration No. S-836  
 (County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of \_\_\_\_\_, I hereby certify that the within instrument was filed in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_ at \_\_\_\_\_ o'clock \_\_\_\_\_ M.

(Register of Deeds)

By \_\_\_\_\_ Deputy