

CERTIFIED LAND CORNER RESTORATION

Index No. U-25

State of Wisconsin }  
County of Lincoln } ss.

History of original corner establishment:

I John H. Fisher do hereby certify that on the 19 day of June, 1979, I found evidence of the South east corner of Section 25 Township 35, North, Range 7, Fourth, Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Date of Original Survey: June 1861  
Survey performed by: Alfred Millard - Deputy Surveyor

Witnesses:  
12" Cedar, S76°W, 25 links  
8" Cedar, N83°W, 10 links  
8" Cedar, S50°E, 29 links  
16" Cedar, N58°E, 36 links

Description of corner evidence found:

Used original distance from small stream as direct witness and line between east one quarter of Section 25 and section corner common to Sections 1,6,31 and 36, T35N, R7E


Resident witnesses:

none

Description of monument and accessories I established to perpetuate the original location of this corner.

Set Lincoln County Berntsen Monument

Witnesses:  
8" Tamarack, N76°E, 23.6 feet  
4" White Birch, S26°E, 19.6 feet  
8" Tamarack, N18°W, 33.0 feet  
10" Tamarack, N2°W, 47.7 feet



○ = Corner monument restored.



Dated at Minocqua, Wis., this 29th day of June, 1979.

Signature John H. Fisher Title Registered Land Surveyor Registration No. S-836  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of \_\_\_\_\_, I hereby certify that the within instrument was filed in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_ at \_\_\_\_\_ o'clock \_\_\_\_\_ M.

(Register of Deeds)

By \_\_\_\_\_ Deputy