

Attachment to Tie Sheet W-13, T35N, R8E

43508332000

I visited the corner on 10/24/2018 to verify the corner and reference tie monumentation. I found the Granite monument, up 12", and all 4 ties from Dennis Roberts (MSA) tie sheet (05/02/2003). The established Coordinates and all 4 ties agree with existing monument.

 *Anthony R. Dallman* 4/02/19

Anthony R. Dallman, PLS-2405


Lincoln County Surveyor



U.S. PUBLIC LAND SURVEY MONUMENT RECORD

NOTE: This form is intended and designed to fulfill all requirements of Wisconsin Administrative Code, Chapter A-E 7.08 U.S. Public Land Survey Monument Record (3)(a)(b)(c)(d)(e)(f)(g)(h)(i). An additional sheet may be added if necessary to conform with said requirements.

(a) Corner location: Township 35 North
 Range 08 East
 Town of HARRISON
 LINCOLN County, Wisconsin



Section 33

(b)(f)(g)(h) Description of monument found at this corner and if it was accepted, state all evidence (material, testimonial, occupational, plats, records, other monuments) used as a basis for accepting. If not accepted or if nothing was found, state evidence used as basis for establishing location. If reestablished through lost corner proportionate methods, indicate all monuments, distances and directions used to establish. Indicate type of monument found or set and sign post.

1865 - Original corner set by Jos. L. Nowlin

1937- Francis Fuchs- set 6"x6" granite stone mounded with stone,
 by proportional measurement.
 Norway Pine 14" N21°E 57.3 Lks.
 W Birch 6" S37°W 40.6 Lks.


2003- I found 6"x6" granite stone mounded with stone.
 Fuchs BT 24" R Pine N21°E 38.82'

Witnessed corner as shown below.

(c)(d)(e) Plan view of corner with ties to at least 4 witness monuments. If in disagreement with previously established corner, show the distances between the two corners and also indicate the ties to the disputed corner.

- FOUND 6"x6" GRANITE MONUMENT
- SET 3/4 ROD WITH ALUMINUM CAP
- T** PLASTIC "T" SIGN SET 1' NORTH

RECEIVED AT LINCOLN COUNTY
 COURTHOUSE THIS 10TH DAY
 OF May 20 03
Tom Deller
 LAND INFORMATION OFFICE



(i) I, Dennis Roberts, Registered Land Surveyor #S-1863, hereby certify that the corner location on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.



Index No. W-13

Dennis B. Roberts
 Signature Date 5/02/03